BRUHATH BENGALURU MAHANAGARA PALIKE
Yelahanka Division, Yelahanka Zone

Executive Engineer
Yelahanka Division
B.B.M.P. Bengaluru - 64
No:EE/YNK-D/E-PMT/04/2014-15 Dated: 31-10-2014

APPROVED TENDER SCHEDULE –'B'

Item No: 60

Name of Work:-Construction of culverts and improvements of drains in Akshayanagara area in Attur ward no:03

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri. M B HOMBAL	
				Rate	Rate in Words
1	KSRRB 300-1,Earth work excavation by manual means in ordinary soil invlving an average horizontal throw up to 2 meters and an average lift uo to 1.5m,excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications(Item no19.1,Page no138,PWD SR 2014-15)	Cum	274.95	74.00	Rupees seventy four only
2	Removing B.S slab of drain and stacking	Sqm	935.55	56.00	Rupees fifty six only
3	Refixing stone slabs of drains and pointing in CM(1:3)	Sqm	935.55	70.00	Rupees seventy only
4	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete do 7.5 cms thick	Sqm	400.95	610.00	Rupees six hundred ten only
5	KSRB 2-2.2 : Earth work excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5m , in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m. specification, specification. No. KBS 2.1(b) / 2.3.5, No. 5/ Item No. 2.4/ PWD SR 2014-15	Cum	17.55	260.00	Rupees two hundred sixty only
6	KSRRB M100-1 Loading and un loading of stone boulder/Stone aggregates/sand/kanker/Moorum.KSRRB M100-1:Placing tipper at loading point,loading with front end loader,dumping,turning for return trip,excluding time for haulage and return trip complete as per specifications(Item no17.1,Page no130,PWD SR 2014-15)	Cum	292.50	68.00	Rupees sixty eight only
7	KSRB 4-1.3:Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @0.57cum machine mixed,machine mixed,concrete laid in layers not exceeding 15cms.thick, well compacted in foundation,including cost of all materials,labour,HOM of machinery,curing complete as per specifications.Specification no KBS4.1,4.2(Item no4.3,Page no12,PWD SR 2014-15)	Cum	2.48	4750.00	Rupees four thousand seven hundred fifty only

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri. M B HOMBAL	
				Rate	Rate in Words
8	KSRB 4.2.2 : Providing and laying in position Reinforced cement concrete of design mix M20 with OPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregates @0.460cum with superplastesisre @ 3lts conforming etc as per specification&direction of the engineer incharge of work(pwd sr2014-15,p.no13,sno4.11)	Cum	10.65	5800.00	Rupees five thousnd eight hundred n only
9	KSRB 4.9.2: Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per specifications.Specification noKBS 4.6.3,TMT bars Fe550(pwd sr2014-15,p.no17,s.no4.46)	Qnt	10.65	7900.00	Rupees seven thousand nine hundred only
10	KSRB 4-6.4 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, attached pilasters,bittresses,buttresses plinth and string course including cost of all materials,labour complete asperspecification. Specification no.KBS 4.6.2(pwd sr2014-15,p.no15/4.31)	Sqm	51.00	290.00	Rupees two hundred ninety only
11	KSRB 5-14: Providing and constructing precast concrete solid blocks with compressive strength not less than 35Kg/sqm with cement mortar 1:4 masonry (quoin, Jamb, closer blocks) with solid concrete blocks of size 40x20x20cms conforming to I.S: 2185/1965 in superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications. (P25/5.27)	Sqm	162.00	990.00	Rupees nine hundred ninety only
12	KSRB 5-15: Providing and constructing Non load bearing wall with cement concrete solid blocks with compressive strength not less than 35Kg/sqm with cement mortar 1:4 masonry (quoin, Jamb, closer blocks) with solid concrete blocks of size 40x10x20cms conforming to I.S: 2185/1965 in superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications. (P25/5.28)	Sqm	162.00	720.00	Rupees seven hundred twenty only
13	KSRRB 4.1:6Providing and laying in position plain cement concrete mix 1:2:4 with cement @240kgs,with 20mm and down size graded granite metal course aggregates @0.69 cum and fine aggregates @0.459cum, machine mixed, concrete laid in layers not exceeding 15cms thick well compacted,in foundation,plinth and cills,including cost of all materials, labour, HOM of machineries, curing complete as per specifications.Specification no4.1,4.2 (Page.12 & Item No. 4.6)	Cum	32.40	5000.00	Rupees five thousand only
14	Providing and fixing Precast RCC Slabs as Per approved design, specification and Direction Engineer-in-Charge. (Approved Data Rate).	Sqm	758.70	1235.00	Rupees one thousand two hundred thirty five only

Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.